

1 **Q. (Reference Application Schedule B, pages 18 and 19 of 98) What would be the**
2 **impact on the cost of the PCB Bushing Phase-out (Pooled) project if the remainder**
3 **of the project were delayed and completed in 2024 consistent with Government**
4 **regulations? What efficiencies have been gained since the project was initiated in**
5 **2017?**

6
7 A. Government of Canada PCB Regulations (SOR/2008-273) require that substation
8 transformer bushings, breakers and instrument transformers with PCB concentrations of
9 greater than 50 ppm be removed from service by the end of 2025. The Company
10 submitted its plan to comply with these regulations in its *2012 Capital Budget*
11 *Application*.¹

12
13 At year-end 2020, there will be 15 substations with PCBs that must be removed prior to
14 year-end 2025.² Delaying this work for completion in 2024 or 2025 would: (i) increase
15 project costs; (ii) increase risks of long-duration customer outages; and (iii) increase
16 project execution risks.

17
18 Increased project costs are driven by the elimination of existing efficiencies.
19 Newfoundland Power has achieved efficiencies by aligning the removal of PCBs with
20 other required substation projects. For example, the removal of PCBs has been
21 completed in conjunction with *Substation Refurbishment and Modernization* projects.
22 This creates efficiencies in project management, staff mobilization and the deployment of
23 portable substations. Completing all required PCB removals in a single year would
24 eliminate opportunities to align the removal of PCBs with other substation work. This, in
25 turn, increases project costs.³

26
27 The increased risk of customer outages is driven by the availability of portable
28 substations. For 8 of the 15 remaining substations, the installation of a portable
29 substation would be required to avoid long-duration customer outages.⁴ Removing PCBs
30 from these 8 substations in a single year would reduce the availability of portable
31 substations to complete other capital projects and to respond to unplanned equipment
32 failures.⁵ This, in turn, increases the risk of long-duration customer outages.

33
34 With respect to increased project execution risks, PCBs have been identified as harmful
35 to the environment. Continuing to leave them in the system longer than necessary

¹ See report *2.3 2012 PCB Removal Strategy* filed with Newfoundland Power's *2012 Capital Budget Application*.

² These substations include 29 pieces of equipment with PCBs that must be removed.

³ For example, the typical cost of installing a portable substation is approximately \$50,000 per installation. Following the current phase-out plan, the removal of PCBs will be coordinated with other substation work in 6 of 8 cases. This coordination alone reduces costs to customers by approximately \$300,000 (\$50,000 x 6 = \$300,000).

⁴ The time required to replace power transformer bushings under a planned outage would exceed a day and is deemed unacceptable. For these 8 substations, it is not possible to transfer customer load to an adjacent substation to avoid customer outages. Portable substation installations are therefore required.

⁵ For example, in 2020 Newfoundland Power experienced the failure of a power transformer at its Bonavista Substation. A portable substation was deployed for approximately 10 months to minimize customer outages.

1 increases the risk of release. Additionally, delaying all remaining work to 2025 would
2 present risks that execution delays could result in non-compliance with Federal
3 Government regulations.

4
5 Based on this assessment, delaying the removal of PCBs in order to complete all work in
6 a single year would be inconsistent with delivery of reliable service to customers at least
7 cost.