

June 28, 2016

Board of Commissioners of Public Utilities
Prince Charles Building
120 Torbay Road, P.O. Box 21040
St. John's, NL A1A 5B2

Attention: Ms. Cheryl Blundon
Director of Corporate Services & Board Secretary

Dear Ms. Blundon:

Re: An Application by Newfoundland and Labrador Hydro (Hydro) pursuant to Subsection 41(3) of the Act for the approval of the Turbine Rehabilitation of Bay d'Espoir Unit 4


Please find enclosed the original and 12 copies of the above-noted Application, plus supporting affidavit, project proposal, and draft order. The proposed project involves the rehabilitation of Bay d'Espoir Unit 4 turbine, which is necessary for the supply of safe and adequate and reliable power to the Island Interconnected System.

Hydro respectfully requests that this application be addressed in an expedited manner in order to complete the work to meet system load, which begins in September, and to ensure the unit is available and reliable for the 2016/17 winter operating season.

Should you have any questions, please contact the undersigned.

Yours truly,

NEWFOUNDLAND AND LABRADOR HYDRO



Tracey L. Pennell
Senior Counsel, Regulatory

TLP/cp

cc: Gerard Hayes – Newfoundland Power
Paul Coxworthy – Stewart McKelvey Stirling Scales
Sheryl Nisenbaum – Praxair Canada Inc.

Thomas Johnson, Q.C. – Consumer Advocate
Thomas J. O'Reilly, Q.C. – Cox & Palmer
Larry Bartlett – Teck Resources Limited

IN THE MATTER OF the *Electrical Power Control Act*, RSNL 1994, Chapter E-5.1 (the *EPCA*) and the *Public Utilities Act*, RSNL 1990, Chapter P-47 (the *Act*), and regulations thereunder;

AND IN THE MATTER OF an Application by Newfoundland and Labrador Hydro (Hydro) pursuant to Subsection 41(3) of the *Act*, for approval of the Rehabilitation of Bay d'Espoir Unit 4 turbine.

TO: The Board of Commissioners of Public Utilities (the Board)

THE APPLICATION OF NEWFOUNDLAND AND LABRADOR HYDRO (Hydro) STATES THAT:

1. Hydro is a corporation continued and existing under the *Hydro Corporation Act, 2007*, is a public utility within the meaning of the *Act* and is subject to the provisions of the *Electrical Power Control Act, 1994*.
2. Hydro is the primary generator of electricity in Newfoundland and Labrador. The largest of Hydro's hydro-electric generating stations is located at Bay d'Espoir. Unit 4 at Bay d'Espoir is a 76.5 MW unit originally built in 1968. In 1994, a new runner was installed at the unit and at that time new primary seals were installed.
3. Seals are key components of hydro-electric units. The seal clearance is the distance between the stationary and rotating wearing rings of a Francis turbine. These seal clearances are designed and set by the manufacture. The purposes of these design seal clearances are for efficiency, hydraulic balance, prevention of rubbing due to misalignment and imbalance, and for cooling between the runner and stationary wear rings.

4. On June 5, 2016 Bay d'Espoir Unit 4 (76.5MW) was removed from service for annual maintenance and to complete other maintenance works. The upper and lower primary seal clearances were measured as part of the inspection and it was determined that they are now less than acceptable for reliable operation.
5. Hydro consulted two external experts for an opinion on the current operability of the turbine seal clearance measurements. Both advised that this condition exposed the unit to a risk that it would not operate reliably without the potential for mechanical damage and a forced outage.
6. The seal clearances had been reducing over time, which is normal, and the work to address this was identified in the 2019 capital plan as part of Hydro's maintenance approach for the hydraulic turbines. However, in this year's detailed inspection and condition assessment it was learned that the clearances reduced faster than anticipated and reinstating proper seal clearances must now take place in 2016.
7. Returning the unit to service without rectifying the reduced clearances would expose the unit to a high risk of mechanical damage and a forced outage that would be between 6 and 8 weeks. Were a forced outage to occur, 76.5 MW of capacity and the associated energy would be unavailable to the Island Interconnected System while the clearances were rectified. Completion of the turbine refurbishment is required to ensure Hydro can provide safe, reliable electrical service to its customers.
8. The scope of work requires the full dismantling of Unit 4. While the unit is fully dismantled, Hydro is proposing to accelerate the remaining tasks of the 2019 planned refurbishment project work into 2016 which will negate the requirement to take an outage of this unit for this work in 2019.

9. The estimated cost of this project is \$1,977,300 and, if commenced by mid-July, is expected to be completed by the end of September.
10. The Applicant submits that the proposed refurbishment of the Unit 4 seals at Bay d'Espoir is necessary to ensure that the Hydro can continue to provide service which is safe and adequate and just and reasonable as required by Section 37 of the Act. An Engineering Report supporting this supplemental capital application is attached.
11. Hydro therefore makes Application for an Order pursuant to section 41(3) of the Act approving the refurbishment of the seals of Unit 4 at Bay d'Espoir, and the completion of certain overhaul work that was originally scheduled for 2019, at an estimated capital cost of \$1,977,300, all as set out in this Application and in the attached project description and justification document.

DATED at St. John's in the Province of Newfoundland and Labrador this 28th day of June 2016.



Tracey L. Pennell
Counsel for the Applicant
Newfoundland and Labrador Hydro
500 Columbus Drive P.O. Box 12400
St. John's, NL A1B 4K7
Telephone: (709) 778-6671
Facsimile: (709) 737-1782

IN THE MATTER OF the *Electrical Power Control Act*, RSNL 1994, Chapter E-5.1 (the *EPCA*) and the *Public Utilities Act*, RSNL 1990, Chapter P-47 (the *Act*), and regulations thereunder;

AND IN THE MATTER OF an Application by Newfoundland and Labrador Hydro (Hydro) pursuant to Subsection 41(3) of the *Act*, for approval of the Rehabilitation of Bay d'Espoir Unit 4 turbine.


AFFIDAVIT

I, Jennifer Williams, Professional Engineer, of St. John's in the Province of Newfoundland and Labrador, make oath and say as follows:

1. I am General Manager, Hydro Production of Newfoundland and Labrador Hydro, the Applicant named in the attached Application.
2. I have read and understand the foregoing Application.
3. I have personal knowledge of the facts contained therein, except where otherwise indicated, and they are true to the best of my knowledge, information and belief.

SWORN at St. John's in the)
Province of Newfoundland and)
Labrador)
this 28 day of June 2016,)
before me:)


Barrister – Newfoundland and Labrador


Jennifer M. Williams

1 (DRAFT ORDER)
2 NEWFOUNDLAND AND LABRADOR
3 BOARD OF COMMISSIONERS OF PUBLIC UTILITIES
4

5 AN ORDER OF THE BOARD
6

7 NO. P.U. __ (2016)
8

9 **IN THE MATTER OF** the *Electrical Power*
10 *Control Act*, RSNL 1994, Chapter E-5.1 (the
11 *EPCA*) and the *Public Utilities Act*, RSNL 1990,
12 Chapter P-47 (the *Act*), and regulations thereunder;
13

14 **AND IN THE MATTER OF** an Application
15 by Newfoundland and Labrador Hydro (Hydro)
16 pursuant to Subsection 41(3) of the *Act*, for
17 approval of the Rehabilitation of Bay d'Espoir
18 Unit 4 turbine.
19
20

21 **WHEREAS** the Applicant is a corporation continued and existing under the *Hydro Corporation*
22 *Act, 2007*, is a public utility within the meaning of the Act and is subject to the provisions of the
23 *Electrical Power Control Act, 1994*; and
24

25 **WHEREAS** Section 41(3) of the Act requires that a public utility not proceed with the
26 construction, purchase or lease of improvements or additions to its property where:

- 27 a) the cost of construction or purchase is in excess of \$50,000; or
28 b) the cost of the lease is in excess of \$5,000 in a year of the lease,
29

30 without prior approval of the Board; and
31

32 **WHEREAS** in Order No. P.U. 33(2015) the Board approved Hydro's 2016 Capital Budget in
33 the amount of \$183,082,800; and
34

35 **WHEREAS** on June 5, 2016, Bay d'Espoir Unit 4 turbine was removed from service and the
36 lower primary seal clearances were reviewed and deemed to be now less than acceptable for
37 reliable operation; and
38

39 **WHEREAS** on June 28, 2016 Hydro applied to the Board for approval to rehabilitate Bay
40 d'Espoir Unit 4 turbine; and
41

42 **WHEREAS** the capital cost of the project is anticipated to be \$1,977,300; and

43 **WHEREAS** the Board is satisfied that the rehabilitation of Bay d'Espoir Unit 4 turbine is
44 necessary and reasonable to allow Hydro to provide service and facilities which are reasonably
45 safe and adequate and just and reasonable.

1 **IT IS THEREFORE ORDERED THAT:**

2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22

1. The proposed capital expenditure to rehabilitate Bay d'Espoir Unit 4 of \$1,977,300 is approved.

2. Hydro shall pay all expenses of the Board arising from this Application.

DATED at St. John's, Newfoundland and Labrador, this day of , 2016.

A REPORT TO

THE BOARD OF COMMISSIONERS OF PUBLIC UTILITIES

	Electrical
	Mechanical
	Civil
	Protection & Control
	Transmission & Distribution
	Telecontrol
	System Planning

Turbine Rehabilitation

Bay d'Espoir Unit 4

June 28, 2016



1 **SUMMARY**

2 On June 5, 2016 Bay d'Espoir Unit 4 (76.5 MW) was removed from service. There were
3 three projects that necessitated Unit 4 to be removed from service: scheduled annual
4 maintenance; refurbishment on the surge tank that serves Units 3 and 4; and replacement
5 of the main inlet valve bypass valves for Units 3 and 4. As part of the annual maintenance,
6 inspections and assessments are completed. Clearances between the upper and lower
7 primary seals and the runner were measured as part of the inspection. The lower primary
8 seal clearances were reviewed and deemed to be now less than acceptable for reliable
9 operation.

10
11 Hydro consulted two external experts for an opinion on the current operability of the
12 turbine seal clearance measurements. Both advised that this condition exposed the unit to
13 a risk that it would not operate reliably without the potential for mechanical damage and a
14 forced outage.

15
16 The lower seal clearances had been reducing over time and the work to address this was
17 identified in the 2019 capital plan as part of Hydro's maintenance approach for the
18 hydraulic turbines. This plan contained a major refurbishment project, including addressing
19 the previously identified reduced seal clearances. However, in this year's detailed
20 inspection and condition assessment, the clearances reduced faster than anticipated. The
21 refurbishment project, which includes re-establishing the clearances, must now take place
22 in 2016. Hydro is proposing to accelerate the remaining tasks of the 2019 planned
23 refurbishment project work into 2016. This then negates the requirement to take an outage
24 for this work in 2019.

25
26 Reinstatement of the lower seal clearances for Unit 4 is required to provide reliable
27 operation through the 2016/2017 winter operating season, as well as through subsequent
28 years. Returning the unit to service without rectifying the reduced clearances places a high
29 risk of mechanical damage to the unit and a forced outage that would be between 6 and 8

1 weeks. If a forced outage were to occur in winter, 76.5 MW of capacity and the associated
2 energy would be unavailable to the Island Interconnected System while the clearances were
3 rectified. Completion of the turbine refurbishment is required to ensure Hydro can provide
4 safe, reliable electrical service to its customers.

TABLE OF CONTENTS

SUMMARY.....	i
1 INTRODUCTION.....	1
2 BACKGROUND.....	3
3 PROJECT DESCRIPTION.....	9
4 JUSTIFICATION	11
4.1 Existing System	11
4.2 Operating Experience	12
4.2.1 Reliability Performance.....	12
4.2.2 Legislative or Regulatory Requirements.....	13
4.2.3 Safety Performance	13
4.2.4 Environmental Performance.....	13
4.2.5 Industry Experience	13
4.2.6 Vendor Recommendations	14
4.2.7 Maintenance or Support Arrangements.....	14
4.2.8 Maintenance History	14
4.2.9 Historical Information.....	14
4.2.10 Anticipated Useful Life.....	15
4.3 Forecast Customer Growth.....	15
4.4 Development of Alternatives.....	15
4.5 Evaluation of Alternatives.....	16
4.5.1 Energy Efficiency Benefits.....	16
4.5.2 Economic Analysis.....	17
5 CONCLUSION.....	17
5.1 Budget Estimate.....	17
5.2 Project Schedule	18

Appendix A – Turbine Generator Assembly

Appendix B – Seal Details

1 **1 INTRODUCTION**

2 Bay d'Espoir Unit 4 is a 76.5 MW hydraulic generating unit that was constructed as part of
 3 the Bay d'Espoir Stage 1 in 1968. It provides electricity to the Island Interconnected System.
 4 Figure 1 is a picture of the Provincial electricity grid showing the location of the Bay d'Espoir
 5 Generating Station.
 6




Figure 1: Provincial Grid

7
 8 In 1994, the original mild steel turbine runner was replaced due to repeated cavitation¹
 9 damage. A stainless steel runner was installed at that time which improved the resistance to
 10 cavitation damage and improved runner efficiency. At that time, the primary seals were
 11 replaced with an aluminum bronze material and machined in place to create the proper
 12 clearance with the new runner. Additional turbine rehabilitation work was carried out

¹ Cavitation is a phenomenon which results in pitting of the runner surfaces.

1 including head cover and discharge ring modifications, wicket gate bushing replacement,
2 carbon seal replacement, and a unit alignment.

3

4 Figure 2 is a photograph of the Bay d'Espoir Generating Station Site.

5



Figure 2: Bay d'Espoir Hydro Generating Station Site

- 1 Figure 3 is a picture of all six 76.5 MW hydraulic generating units inside Power House #1 at
- 2 Bay d'Espoir.
- 3



Figure 3: Bay d'Espoir Hydraulic Generating Units 1 - 6

4

5 **2 BACKGROUND**

6 The asset management strategy for Hydraulic turbine generators includes three distinct
7 points of intervention:

- 8 1. The first is an annual preventative maintenance inspection that primarily consists
9 of non-intrusive visual inspections and tests, as well as the replacement of some
10 regular wear parts, including carbon brushes.

- 1 2. On a six year frequency, a unit overhaul is performed that consists of a partial
2 dismantle of the unit (generator rotor is removed) to perform more intrusive
3 condition based inspection and rehabilitation of the unit.
- 4 3. Based on equipment condition obtained through the annual inspection and the 6
5 year overhaul, a major refurbishment of turbine components is planned and
6 placed in the capital budget plan. This refurbishment requires a complete unit
7 dismantlement to refurbish turbine components including the runner (as
8 required), turbine seals, wicket gate components, and other items that require
9 attention based on their condition. The actual timing is based on condition. This
10 intervention is currently in the capital plan, with a program for the
11 refurbishment of the Bay d'Espoir turbines starting in 2019.

12

13 One of the tasks in Hydro's asset management program for hydraulic units is the
14 measurement of the upper and lower primary seal clearances. The seal clearance is the
15 distance between the stationary and rotating wearing rings of a Francis turbine. These seal
16 clearances are designed and set by the manufacture. The actual design clearance depends
17 on both the size and speed of the unit. These clearances should not change unless the
18 wearing rings are affected by phenomena such as wear (cavitation, corrosion, erosion) or
19 distortion or the runner incurs axial movement due to bearing wear or misalignment. The
20 purposes of these design seal clearances are for efficiency, hydraulic balance, prevention of
21 rubbing due to misalignment and imbalance, and for cooling between the runner and
22 stationary wear rings.

23

24 The measurements taken are compared against previous readings and design clearances.
25 Depending on the results of the measurements, Hydro may consult with internal and
26 external turbine experts to determine if any intervention is required.

27

28 The lower primary seal clearance measurements taken in June 2016 for Unit 4 showed an
29 accelerated reduction in the amount of the clearance when compared to recent previous

1 readings shown in Table 1.² In prior years, the clearances had been trending away from
2 design clearance, but at a rate that was not considered urgent for action. A trending away
3 from design is an indicator that future action is required, but is not atypical for hydroelectric
4 units. The work to address the reduced clearances was identified in the 2019 capital plan as
5 part of Hydro's maintenance approach for the hydraulic turbines. This plan contained a
6 major refurbishment project, including addressing the previously identified reduced seal
7 clearances.

8

9 To date on the various Bay d'Espoir units, the diametric³ clearance at the seals has generally
10 been such that a maintenance correction can be completed to re-establish acceptable
11 clearances when measured radially⁴. A maintenance correction would be re-aligning or re-
12 centering the runner. For the June 2016 Unit 4 seal clearance measurements, it was clear
13 that the remaining diametric and radial clearances were not sufficient and that an
14 alignment (or re-centering) could not provide appropriate clearance.

15

16 As a result of the measured reduced clearances, Hydro contacted external (Hydro Expertise
17 and Voith Hydro) experts, and performed further testing at their request to gather more
18 information so they could make an informed recommendation. Both external parties
19 consulted subsequently recommended that corrective action must be taken to restore the
20 seal clearances to their original design in order to operate reliably through the winter
21 operating season and for future operation.

22

23 In addition to external expertise, additional documented guidance was sought to inform
24 Hydro what level of required action would be required. Section 6.6.2 of Part V of the CEATI⁵

² Potential cause of loss of clearance discussed further in this section.

³ Diametric clearance is the total clearance at the seal. It is the sum of the two radial clearance measurements.

⁴ The radial clearance is the measurement from one surface to the other. The clearance can be increased or decreased by tilting the shaft to increase or decrease the clearance. If the shaft was tilted to increase the radial clearance on one side of the runner, the alternate side would decrease, and vice versa.

⁵ CEATI: The Centre for Energy Advancement through Technological Innovation (CEATI) is a user-driven organization committed to providing technology solutions to its electrical utility participants, who are brought together to collaborate and act jointly to advance the industry through the sharing and developing of practical and applicable knowledge.

1 publication: "Hydroelectric Turbine-Generator Units Guide for Erection Tolerances and Shaft
2 System Alignment" was reviewed and compared to the recent measurements. The
3 clearances were found to be not acceptable when compared to the CEATI guide, which
4 concurred with the external expertise consulted. For reference, see Table 1 for the current
5 readings as well as previous readings and CEATI recommended clearances.

6
7 The clearance measurements are recorded, using a clockwise rotation looking down from
8 the top of the rotor and using the stator or stationary parts as the reference system. Figure
9 5 below is a representation of where the readings are taken as if you were looking down
10 onto the rotor (or onto the runner).

11
12 To provide perspective, many plastic ID cards are about 30 thousandths of an inch thick. As
13 is the case with any hydroelectric generating unit, appropriate clearances are generally
14 measured in the thousandth of an inch and therefore, repeated measurements are taken by
15 different skilled persons to ensure measurement error is minimized, and that the clearances
16 are confirmed as accurate.

17
18 Figure 4 shows a close up detail of the seal area of the turbine. Appendix A shows a large
19 cut away of the turbine generator assembly. In Appendix A, the area depicted below in
20 figure 4 is located by detail 47. Appendix B shows additional detail of the seal area.




Figure 4: Close up detail of the lower seal area




Figure 5: Position of the clearance readings as they relate to the data in Table 1

Table 1: Clearances between Runner and Seal⁶

	US	DS	US+DS	A1	A2	A1+A2
Design Min	0.040	0.040	0.800	0.040	0.040	0.080
Design Max	0.055	0.055	0.110	0.055	0.055	0.110
CEATI Max	0.083	0.083	0.166	0.083	0.083	0.166
CEATI Min	0.020	0.020	0.040	0.020	0.020	0.040
1994	0.035	0.040	0.075	0.040	0.035	0.075
2009	0.050	0.043	0.093	0.014	0.025	0.039
2011	0.068	0.068	0.136	0.012	0.025	0.037
2012	0.065	0.027	0.092	0.015	0.017	0.032
2016	0.067	0.035	0.102	0.005	0.015	0.020

Note for the table below: US = up stream, DS = down stream, and both of these are considered "radial" measurements; US+DS, as well as A1+A2 are added together to get a "diametric" measurement.

1

2 The lower seal clearances were taken in 1994, as part of the new runner installation, and
 3 while they were not reinstated to the original installation design clearance, they were
 4 acceptable for long term operation. The clearance measurement was taken in 2011 as part
 5 of the unit overhaul and the readings were also taken in 2009 and 2012 as the opportunity
 6 presented itself with the unit down for other reasons.

7

8 Hydro took seal clearance measurements of all Bay d'Espoir units in 2016 as part of
 9 information gathering for the future refurbishment program that was intended to start in
 10 2019 with Unit 4. Based upon the material increase in the clearance loss measured in 2016,
 11 Hydro has now instituted annual lower seal clearance measurements.

12

13 Prior to the readings being taken in 2016, as part of the currently scheduled unit overhaul
 14 for Unit 4 in 2017, Hydro would have taken the readings in 2017 to continue to monitor the
 15 clearances to determine if action was required sooner than the planned turbine
 16 refurbishment in 2019. The major intervention to re-establish design clearances was
 17 planned to occur in 2019 with the refurbishment project.

⁶ The seal clearance readings for the years between 1994 and 2009 are in storage and at the time of this proposal, are being retrieved for completeness of the record.

1 There are various potential causes for seal clearance loss. A common reason is that the
2 concrete behind the seal is deteriorated and voids have developed, allowing the seal to
3 deform away from circular and ultimately become 'oval' thereby changing the clearance.
4 This appears to be the case when examining the Table 1 data. The US+DS diametric
5 clearances have actually increased, while the A1+A2 diametric clearances have decreased,
6 indicating the seal is 'ovalling'. Hydro has also performed hammer tests⁷ and the results
7 further suggest that there are voids that have developed now that the concrete is almost 50
8 years old. When this occurs, utilities will undertake to grout the voids as part of the work to
9 reestablish the seal clearance.

10

11 The 2016 clearance measurements for the other units at Bay d'Espoir currently do not
12 require a major intervention. Units 1, 2, 3, 6, and 7 have seal clearances within acceptable
13 tolerances. Unit 5 has a seal clearance measurement that requires further review, and this
14 review is being undertaken this summer. However, based upon the initial measurements, it
15 is expected that the maximum intervention that may be required on Unit 5 this year is a re-
16 centering of the unit. Essentially, there is enough diametric clearance available on Unit 5
17 that a re-centering of the unit can likely reestablish clearances to acceptable levels. If a re-
18 centering is required, this work will be scheduled to coincide with other capital work
19 planned that requires that Unit 5 to be out of service and therefore there is not expected to
20 be an additional impact on the unit outage timeline.

21

22 **3 PROJECT DESCRIPTION**

23 In order to reestablish the required seal clearances for safe, reliable operation, the scope of
24 work consists of the full dismantling of Unit 4. As the unit would be fully dismantled, Hydro
25 is proposing to complete the seal clearance reestablishment as part of the full scope of the
26 refurbishment that was planned for 2019, including a thorough inspection, and replacing or
27 refurbishing worn components found during the inspection. Completion of this work during

⁷ A hammer test is performed by tapping the steel liner with a hammer to listen for hollow sounds. This is similar to tapping a wall when looking for a stud to mount a picture.

1 this major disassembly then negates the need for the refurbishment project that was
2 previously planned in 2019.

3

4 The items in the scope of work in the turbine refurbishment project that address the
5 identified reduced seal clearances include:

- 6 • Runner lower primary seal grouting and machining to design clearance; and
- 7 • An inspection of the upper primary seal, to be machined if required.

8

9 The remaining turbine refurbishment tasks will include:

- 10 • An inspection of the head cover and bottom ring/bushings. Worn parts will be
11 replaced since they can only be replaced with the unit completely dismantled;
- 12 • An inspection of the operating ring bearings and linkage bushings. Worn
13 components will be replaced where practical, and refurbished otherwise;
- 14 • All wicket gate stem “V” packing will be replaced;
- 15 • Runner cavitation will be refurbished as close to its original condition as
16 practical; and
- 17 • An inspection of the concrete behind the scroll case and draft tube. Concrete
18 grouting will be performed where/if required.

19

20 Hydro proposes that performing the full turbine refurbishment scope of work is appropriate
21 at this time. The seal clearance re-establishing work requires the full dismantlement of the
22 unit, which is not currently part of any preventative maintenance task and takes place only
23 for major capital refurbishment work. To complete a turbine refurbishment, the unit
24 requires being fully dismantled again. Completing the complete scope of turbine
25 refurbishment would include the seal clearance work and removes the need for a full
26 dismantlement and associated refurbishment in 2019.

27

28 Completing the full refurbishment work concurrently with the seal clearance
29 reestablishment adds less than one week to the outage for the seal clearance work alone.

1 The majority of the remaining tasks can occur while the lower primary seal is being
2 refurbished. Therefore, the overall outage time is not materially impacted by performing
3 the full refurbishment scope of work described above. Further, completing the
4 refurbishment work as part of this project saves the costs associated with the disassembly
5 and reassembly in the future previously planned project. The disassembly and reassembly
6 tasks are approximately 5 weeks duration. Hydro estimates there is an avoidable cost by
7 completing this work now, as opposed to completing the remaining refurbishment work in
8 2019, of between \$400,000 and \$500,000.

9

10 The execution of the seal clearance work will be overseen by external experts for all aspects
11 of the seal reestablishment.

12

13 **4 JUSTIFICATION**

14 The clearance readings for the Unit 4 lower primary turbine seal are unacceptable for the
15 return of the unit to service. An independent consultant with expertise in hydraulic
16 generating units and the original equipment manufacturer (OEM) turbine expert both
17 recommended that the unit condition is not acceptable to return it to service.

18

19 Re-establishing the seal clearances is required to avoid a potential on-line failure given the
20 risk of the runner contacting the stationary seal due to the lack of sufficient clearance.

21

22 **4.1 Existing System**

23 Unit 4 is a 76.5 MW vertical Francis hydraulic generating unit constructed in 1968. The
24 runner was replaced in 1994. As part of the runner replacement, other components
25 including the primary stationary seals, and wicket gate bushings were replaced to complete
26 the refurbishment.

27

28 Bay d'Espoir Unit 4 is part of the generation capacity for the Island Interconnected System.

29 If this unit is not returned to service, the capacity and energy supplied by this unit would

1 remain unavailable until the work could be completed during the next planned outage.

2

3 **4.2 Operating Experience**

4 All units at Bay d'Espoir are measured for seal clearances as part of the preventative
5 maintenance program. It is normal for aged units to experience seal clearance loss (often
6 through 'ovalling') and therefore, utilities typically measure and trend this as part of their
7 asset management program. Bay d'Espoir Units 1-6 lower seal readings demonstrate they
8 all have been 'ovalling' over time, which is not atypical. This requires monitoring and action
9 as the clearances approach a certain level, and urgent action when the rate of loss
10 increases. In addition to consulting outside experts, Hydro compares the amount of seal
11 clearance to technical guides to determine when major intervention is required.

12

13 Design clearance is no longer being maintained on the Bay d'Espoir units and this is not
14 atypical for the age of the units, but the unit that currently requires intervention is Unit 4
15 with clearances as low as 5 thousandths of an inch being recorded between the stationary
16 seal and runner. Unit 5 has clearances being evaluated further this summer to determine if
17 a re-centering is required. A re-centering can typically take place over one to two weeks,
18 and does not require disassembly. All other units are above guide documents minimums
19 and do not require intervention at this time.

20

21 **4.2.1 Reliability Performance**

22 If the seal reestablishment work is not completed and Unit 4 is returned to service, there is
23 a potential for there to be a contact between the primary seal and the runner. Were this to
24 occur, it would result in an extended unplanned outage that would require a full
25 dismantlement of the unit. If the unit fails on-line due to this issue leading into or during the
26 winter operating season, 76.5 MW would be unavailable for system capacity and energy for
27 the period that the unit was undergoing refurbishment.

28

29 Further, currently, there is no known mechanical damage on this unit due to the reduced

1 clearances. If the unit is returned to service with reduced clearances, a risk exists that
2 mechanical damage would occur if the runner and seal were to make contact and require
3 more extensive work than is currently contemplated in this proposal. It is reasonably
4 expected the mechanical damage would require additional downtime to rectify when
5 compared to the amount of time required to reestablish clearances when no contact has
6 been made. The amount of additional time that would be required would depend upon the
7 nature and extent of the damage that would occur.

8

9 **4.2.2 Legislative or Regulatory Requirements**

10 There are no legislative or regulatory requirements associated with this project.

11

12 **4.2.3 Safety Performance**

13 An on-line failure of the unit due to this clearance issue is not expected to create a safety
14 hazard for Hydro employees. However, were an on-line failure to occur at a time when the
15 unit was loaded above 50 MW, it would most likely cause an under frequency load shedding
16 event for the Island Interconnected System.

17

18 **4.2.4 Environmental Performance**

19 This project does not impact environmental performance.

20

21 **4.2.5 Industry Experience**

22 A unit at Churchill Falls had to be refurbished due to contact between the rotating and
23 stationary parts during a manual rotation and this resulted in an extended outage. Hydro's
24 consultant at Hydro Expertise shared an example about a runner at a different site within
25 Newfoundland that seized in operation from galling which was caused by the runner and
26 the primary stationary seal making contact.

27

28 There are numerous examples of seal clearance loss over time at various utilities. Due to
29 the frequency of this experience, CEATI published the guide "Hydroelectric Turbine-

1 Generator Units Guide for Erection Tolerances and Shaft System Alignment” to compile its
 2 member utilities’ experiences, and to develop and share required clearances and
 3 recommendations as to when action is required.

4

5 **4.2.6 Vendor Recommendations**

6 Voith Hydro, the OEM for this runner, recommended that Hydro not return the unit to
 7 service until the seal clearance is returned to its design specification.

8

9 **4.2.7 Maintenance or Support Arrangements**

10 Hydraulic generating units are inspected and maintained by Hydro Operations.

11

12 **4.2.8 Maintenance History**

13 Table 2 shows the maintenance history for the Bay d’Espoir Unit 4 Turbine.

14

Table 2: Bay d’Espoir Units 4 Turbine Maintenance History

	BDE Unit 4 Turbine		
Year	Preventative Maintenance	Corrective Maintenance	Total Maintenance
2011	\$13,021	\$138	\$13,159
2012	\$6,473	\$1,499	\$7,972
2013	\$5,034	\$3,179	\$8,213
2014	\$12,426	\$2,642	\$15,068
2015	\$1,599	\$4,699	\$6,298
2016 ⁸	\$1,922	\$134	\$2,056
Total	\$40,475	\$12,291	\$52,766

15

16 **4.2.9 Historical Information**

17 Bay d’Espoir Unit 3 was successfully realigned in 2015 to accommodate reduced lower seal
 18 clearance. The unit had a radial clearance of 5 thousandths of an inch on the lower primary
 19 seal. The unit did not require the same major intervention now required on Unit 4 because
 20 there was enough diametric clearance to allow the unit to be aligned such that enough
 21 clearance was obtained radially.

⁸ 2016 is an incomplete year, and includes costs to May 2016.

1 Bay d'Espoir Unit 2 (sister unit to Unit 4) was removed in 2002 to grout and machine the
2 lower primary seal to avoid making contact between the runner and the primary seal. The
3 Unit 2 work was performed in a planned fashion based on decreased readings in a relatively
4 short period of time after the new runner was installed in 1993.

5

6 **4.2.10 Anticipated Useful Life**

7 The proposed work for this unit is part of a normal refurbishment to allow the generating
8 unit to achieve its anticipated maximum normal useful life. The currently planned
9 refurbishment for Unit 4 in 2019 would be removed from the capital plan if this project with
10 the full scope of turbine refurbishment, including the seal clearance re-establishment.

11

12 **4.3 Forecast Customer Growth**

13 Forecasted customer growth is not applicable to this project.

14

15 **4.4 Development of Alternatives**

16 Alternatives were considered;

- 17 1. Return the unit to service as is, and address the seal clearance in the next major
18 outage in 2017 as part of the capital budget, or wait until the 2019 major turbine
19 refurbishment;
- 20 2. Reestablish the seal clearances prior to returning the unit to service through the
21 advancement of the previously planned turbine refurbishment in 2019; and,
- 22 3. Reestablish the seal clearances prior to returning the unit to service but not
23 advance the remaining tasks of the turbine refurbishment in 2019.

24

25 Alternative 1

26 Allowing the unit to return to service in its current condition with a plan to perform the
27 turbine refurbishment as part of the 2017 capital submission or as part of the previously
28 planned 2019 major turbine refurbishment requires the tolerance for a risk of failure during
29 operation. This would result in lost generation capacity for the island. Hydro notes that

1 running at reduced load on this unit does not reduce the risk as the unit still rotates at the
2 same speed no matter the loading and therefore runs the same risk for contact and a forced
3 outage. Hydro does not propose this alternative as an appropriate course of action.

4

5 Alternative 2

6 Due to the degree of clearance loss between the rotating runner and the stationary seal,
7 there is a reasonable likelihood of a forced outage due to the runner contacting the seal. It
8 was recommended by an independent consultant and an OEM turbine expert to re-instate
9 the clearance to acceptable levels prior to returning the unit to service. Both external
10 opinions were arrived at independently. This alternative is more appropriate than
11 Alternative 1 with respect to reliable operation leading into the winter operating season.
12 Completion of the whole turbine refurbishment work addresses the seal clearance and
13 provides a refurbished unit at the conclusion of this work.

14

15 Alternative 3:

16 The difference between Alternative 2 and Alternative 3 is that in Alternative 3 Hydro would
17 not proceed with the full scope of the turbine refurbishment work during the seal clearance
18 reestablishment work. This alternative requires the unit to be dismantled again in 2019,
19 keeping the downtime in the schedule, as well as the extra costs. Completing the
20 refurbishment work now in parallel with the seal clearance reestablishment avoids extra
21 downtime and additional disassembly and reassembly costs in 2019.

22

23 **4.5 Evaluation of Alternatives**

24 Hydro proposes that Alternative 2 be approved, that the appropriate alternative is to
25 complete the seal clearance re-establishment work as well as the remaining tasks of the
26 turbine refurbishment work that had been planned for 2019.

27

28 **4.5.1 Energy Efficiency Benefits**

29 There are no energy efficiency benefits that can be attributed to this project.

1 **4.5.2 Economic Analysis**

2 An economic analysis was not performed in this instance as Hydro proposes the unit must
3 have its clearances reestablished prior to returning the unit to service.

4

5 **5 CONCLUSION**

6 This project is required to ensure that a reliable energy supply is available for the customers
7 of the Island Interconnected System. Since the seal clearance is below an acceptable level to
8 return the unit to service, reestablishing the clearances now is being proposed as the only
9 viable alternative to avoid the risk of near term unplanned failure. Advancing the 2019
10 work, which includes the seal clearance work, will avoid additional downtime and costs that
11 would be incurred in 2019 so it is also proposed that this work be completed in 2016.

12

13 **5.1 Budget Estimate**

14 The budget estimate for this project is shown in Table 3.

15

Table 3: Project Budget Estimate

Project Cost: (\$ x1,000)	<u>2016</u>	<u>2017</u>	<u>Beyond</u>	<u>Total</u>
Material Supply	86.0	0.0	0.0	86.0
Labour	301.3	0.0	0.0	301.3
Consultant	0.0	0.0	0.0	0.0
Contract Work	1,230.0	0.0	0.0	1,230.0
Other Direct Costs	16.2	0.0	0.0	16.2
Interest and Escalation	17.1	77.5	0.0	17.1
Contingency	326.7	0.0	0.0	326.7
TOTAL	1,977.3	0.0	0.0	1,977.3

1 The above budget is based on a budgetary estimate for a contractor to perform the majority
 2 of the work, and there are tasks that must be completed by contractor forces due to the
 3 highly specialized nature of the work. Hydro is exploring possibilities to do some of the
 4 work with its own forces which would lower the cost of the project. However, due to other
 5 project commitments, Hydro will be able to deploy its own resources to this project only if
 6 this project is approved and commenced with minimal delays.

7

8 **5.2 Project Schedule**

9 The anticipated project schedule is shown in Table 4. These are tentative dates and reflect
 10 an early approval by the Board of Commissioners of Public Utilities (the Board). Hydro also
 11 notes that Units 3 and 4 are currently removed from service until the end of July for the
 12 Surge Tank 2 refurbishment work.

13

Table 4: Project Schedule


Activity	Start Date	End Date
Contract Award	July 8, 2016	
Engineering and Material Procurement		July 13, 2016
Contractor Mobilize	July 15, 2016	
Seal refurbishment	July 18, 2016	July 24, 2016
Unit reassembly, and start-up	July 25, 2016	August 12, 2016
Project Closeout	September 30, 2016	N/A

14

15 Hydro recognizes that the schedule reflected above is aggressive. Further, the schedule
 16 reflects an expedited regulatory process. The system load begins to increase in September
 17 and if the project schedule moves into September and Unit 4 is not yet returned to service,
 18 the increased load along with Unit 4 at Bay d'Espoir being unavailable increases the
 19 likelihood that Hydro would need to put a second unit on at Holyrood, which has the
 20 potential for associated additional costs for customers.

21

22 This work is being proposed as a supplement to the 2016 Capital Program to ensure that the
 23 unit is available and reliable for the 2016/17 winter operating season. Submitting this
 24 request as a part of the 2017 Capital Program would result in this unit being unavailable for
 25 the 2016/17 winter operating season.



ID	Description	Dwg. No.
Canadian General Electric Drawings		
1	STATOR	499C565BD
2	GENERATOR HOUSING ASSEMBLY	292D602BR
3	ROTOR ASSEMBLY	499C583BG
4	UPPER BRACKET	499C106BE
5	COLLECTOR ASSEMBLY	499C140BJ
6	BRUSH	499C118CH
7	SUPPORT FOR BRUSH RIGGING	704C669AA
8	ROTOR SPIDER	292D644BJ
9	ROTOR RIM PLATE	499C04DD
10	ROTOR FANS & COVERS * (UNITS 5, 6)	499C122CK
11	STATOR PUNCHING	599B106DJ
12	STATOR WINDINGS	591E111AP
13	STATOR COIL SUPPORT	713D221
14	STATOR FLANGE	599B100CD
15	LOUVERS	292D654BJ
16	SURFACEAIR COOLER	499C110BK
17	BRAKES AND JACKS	945C534
18	OIL BAFFLE	499C137CJ
19	GENERATOR GUIDE BEARING	292D623BW
20	COOLING COIL AND BAFFLE	292D621BR
21	MAIN BRACKET	292D601BP
22	GENERATOR SHAFT	599B111BM
40	STATIONARY RING	
41	ROTATING RING	
44	BASE RING	
50	PNG ASSEMBLY	92-301-953
51	SHROODS (UNITS 5 & 6 ONLY)	7677D219AA
CANADIAN ALLIS CHAMBERS DRAWINGS		
23	SHAFT COUPLING BOLTS	92-217-030
24	COUPLING GUARD	92-301-409
25	TURBINE SHAFT	92-401-480
26	TURBINE BEARING COOLER	92-301-413
27	SERVO-MOTOR ASSEMBLY	92-401-132
28	LOWER OIL PAN HOUSING	92-401-130
29	OPERATING RING	92-401-120
30	WICKET GATE LEVER	92-301-393
31	CARBON SEAL ASSEMBLY (HUHN)	92-401-631
32	HEAD COVER ASSEMBLY	92-401-117
33	WICKET GATE ASSEMBLY	92-501-584
34	GUIDE BEARING ASSEMBLY	92-401-227
35	TURBINE PIT LINER	92-401-126
36	FLOOR PLATES / SUPPORTS	92-301-439
37	SPIRAL CASE ASSEMBLY	92-301-401
38	SPIRAL CASE MANHOLE	92-301-405
39	DRAFT TUBE LINER	92-401-140
40	DRAFT TUBE MANHOLE	92-301-444
52	TABLE HEAD COVER EXTENSION	92-301-884
53	STAY RING	92-401-485

ID	Description	Dwg. No.
VOITH HYDRO DRAWINGS (RUNNER REPLACEMENT)		
41	HEAD COVER WEARING RING	2622-1967
42	RUNNER CROWN	2622-1947
43	RUNNER ASSEMBLY	2622-1956
44	RUNNER COUPLING STUD	2622-1951
45	DISCHARGE RING WEARING RING	2622-1966
46	RUNNER BAND	2622-1948
47	DISCHARGE RING INSERT	2622-1985
48	SEAL CLEARANCE MEASUREMENT POCKET	2622-1986
49	RUNNER CONE	2622-1983
54	BOTTOM RING	92-401-124

NOTICE:
This drawing contains intellectual property of Newfoundland and Labrador Hydro (HYDRO) and shall not be copied or distributed in whole or in part without prior written consent from HYDRO. Use of the drawing shall be restricted to purposes of prosecution of a contract with HYDRO.

HYDRO NEWFOUNDLAND AND LABRADOR HYDRO

**BAY D'ESPOIR GENERATING STATION
TURBINE / GENERATOR ASSEMBLY
UNITS 1 - 6**

ELECT.	SCALE:	None
CIVIL	DESIGNED:	
TRANS.	DRAWN:	K.B.Ricketts
MECH.	DATE:	95-12-08
P&C	CHECKED:	
TELC.	APPROVED:	


W.D. NO.	DWG. NO.	B1 - 2107 - M - 80	REV. 0
----------	----------	--------------------	--------

DWG. NO.	TITLE	NO.	DATE	DESCRIPTION	DWN.	DESIGN.	CHK.	APP'D
	REFERENCE DRAWINGS	1	03-01-10	UPDATED STATIONARY RING	K.B.R.			
REVISIONS								

NOTE:
 THIS DRAWING IS USED ON UNITS 1 THRU 6 EXCEPT FOR SPACERS AT LOCATION (B-6) WHICH ARE USED ON UNITS 4 THRU 6 ONLY.


Appendix B

REVISIONS	
(A-6) 27 WAS 20	DED RDS
(B-3) 30 WAS 25	
01 DCS 8-3-93	DED RDS
REVISED FOR AS BUILT CONDITION PER CUSTOMER PRINT DATED 6-25-96	
02	DED 10-28-96




SHAFT/RUNNER COUPLING PRESTRESS DETAIL.
 PRESTRESS TO 1750 KG/CM (125,000 PSI)
 USING HYDRAULIC TENSIONER FOLLOW INSTRUCTION
 SUPPLIED WITH TENSIONER

- (0121/10) TENSIONER
- (0121/11) INTENSIFIER
- (0121/12) RIGIDS
- (0121/13) SPARES




DETAIL A
 SCALE 1:1

Surface to be machined May 2002



DETAIL B
 SCALE 1:1

METRIC FILE NO. 9972



Project BAY D'ESPOIR		Contract No. 35243	
THIS SCALE PROJECT: NEWFOUNDLAND AND LABRADOR HYDRO		Unit	kg
UNLESS OTHERWISE SPECIFIED, ALL DIMENSIONS ARE IN MILLIMETERS AND DECIMALS THEREOF.		Material/Spec	
Date	DED	Platform No. Etc	
Drawn	MLS	Check Eng	RDS
Date	10-21-92	Title	FIELD ASSEMBLY
Scale	1:5		
Drawing No. 2622-1988		Sheet	1 of 1
2622-2849 SPACER (UNITS 5 & 6)		Rev	02
Dwg. No. 2622-2849		Rev	02
CROSS REFERENCES		Rev	A0